

July 8, 2020

Mr. Michael Terpinski  
Ohio EPA, NWDO, DERR  
347 North Dunbridge Road  
Bowling Green, OH 43402

**Re: EnviroSAFE Services of Ohio, Inc.  
EPA Identification Number: OHD 045 243 706  
June 2020 Progress Report**

Dear Mr. Terpinski:

In accordance with Condition E.13 of its Ohio Hazardous Waste Facility Installation and Operation Permit (the "Permit"), EnviroSAFE Services of Ohio, Inc. ("ESOI") hereby submits this progress report to the Ohio Environmental Protection Agency ("Ohio EPA") for the period beginning June 1, 2020 and ending June 30, 2020.

### **Corrective Measures Implementation ("CMI"):**

#### **Project Activities:**

During this reporting period, CMI activities included the following:

1. Start-up of SWMU 5 LNAPL Solar Sipper System on June 24, 2020;
  - gravel path and parking area was added to impede vegetative growth and provide a parking spot for future pumping/removal of the oil storage drums; and
2. Leachate system maintenance included:
  - Inspection of piezometers and recovery wells on SWMUs 5, 6, and 7:
    - Recorded liquid level at each location with a control panel;
    - Verified functionality of all pumps without a control panel;
  - DPW-19: Observed to be above the Hi Point – Globe valve was exercised, panel power was cycled on and off, and began pumping within normal intervals;
  - NRP-27: Transducer was reading very low – Transducer was pulled, cleaned, and replaced in well. Appeared to be working as designed;
  - NRP-30, 34, and 35: Yield tests performed;
  - SWMU 6: Pumps shut down due to electrical issue – Fixed loose connection on NRP-33 pump starter, fixed loose connection on NRP-25 pump switch, disabled RW-9 pump starter (not part of active network), and repaired faulty tank level indicator;

- SWMU7: Power lost to all pumps on June 22, 2020 due to grass mowing incident – electrician scheduled to repair junction box that was mowed over and markers installed to prevent future recurrence;
- SWMUs 5 & 6 Caps: Vehicle rut repair;
- SWMU 5 Compressor: Drained moisture from controller; and
- SWMU 6 Compressor: Emptied buckets, observed regulator leaking around gauge, and Compressor attic fan was observed to be functioning as designed.

**Summary of All CMI-Related Contacts with the Public:**

ESOI has not had any related contacts with the public during this reporting period.

**Summary of Potential or Encountered Problems and Rectification Actions:**

There is nothing to report in association with this topic for this reporting period.

**Projected Work:**

During the next reporting period it is anticipated that the following activities will occur:


1. Continued construction for replacement of AOC 3 (Building C) – complete installation of heat and air compressor system;
2. Dewatering under SWMU 9 cap surface in preparation for recapping project;
3. Mark location of tanks and utility vaults at SWMU 8 for and closure;
4. Repair electric junction box at SWMU 7;
5. Order part and repair regulator leak around gauge on SWMU 6 compressor when part is received – this issue does not impact system operation;
6. Seed areas of bare soil and fix ruts as needed;
7. Evaluate functionality of air system on SWMU 6;
8. Continued redevelopment of leachate extraction wells in accordance with priority list, with the siltiest wells being addressed first as time and weather allows; and
9. Continued operation and maintenance of the leachate extraction systems on SWMUs 5, 6, and 7.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Mr. Michael Terpinski  
July 8, 2020  
Page 3

If you have any questions, please do not hesitate to contact Stephen DeLussa at (215) 659-2001 ext. 15.

Sincerely,

A handwritten signature in black ink, appearing to read 'D. Roberts', with a long horizontal line extending from the top of the signature towards the right side of the page.

Douglas E. Roberts  
President

cc: Stephen DeLussa, Envirosource Technologies, Inc.  
Mark Nielsen, Ramboll

Michael Momenee, The Mannik & Smith Group